

## Busselton DN375MM Water Pipeline Installation



### Project Description

Leeuwin Civil were engaged to install approximately 1620 metres of 375mm PVC Class 12 pipe, as part of the capital works expansion program to increase water main capacity for the Busselton Water Board.

All infill works along existing road reserves owned by the City of Busselton had to be carried out under the City's requirements.

All verge works on private residential verges also had to be restored to pre-existing states.

### Scope of Works

- service location;
- trenching, backfilling and Installation of 1.62km of 375mm PVC Class 12 pipe; and
- reinstatement of:
  - road crossings,
  - road reserves,
  - footpaths,
  - kerbing,
  - residential driveways, and
  - vegetation as necessary.

#### Location

Busselton, WA

#### Dates

Jan 2016 - Feb 2016

#### Client

Busselton Water Board

#### Project type

Underground Infrastructure

#### Cost

\$300,000

#### Job Number

1814

#### Referee

Brad Decorsey  
Busselton Water  
(08) 9781 0512