



# Alpha Road 100AC Water Mains Replacement



#### Location

Busselton, WA

#### Dates

Apr 2016 - Jun 2016

#### Client

Busselton Water Board

#### Project type

Underground Installation

#### Cost

\$50,000

## Project Description

Leeuwin Civil were engaged to install 348m of new 100mm PVC water main at Alpha Road in Busselton. The project included all re-instatement works affected by the water main construction.

Hand plunking was used to excavate around tree root systems during works. This ensured the preservation and protection of vegetation within the site footprint.

The installation main replaced the existing 100AC main that was left dead in-situ.

## Scope of Work

- installation of new 100mm PVC water main; and
- reinstatement of roads, verges & footpaths.

#### Job Number

1822

#### Referee

Brad Decorsey,  
Busselton Water,  
(08) 9781 0512